

Remote Launch Control System Setup

For UXO CF3 and SF1

Remote Launch Control System Setup Procedure

	Contents
	This document contains the following:
	Indoor Setup and checks
	Outside Setup
	Outside System Checks
	Required Items
	Things you'll need to perform this procedure
1	☐ Client Side Box (yellow pelican case)
2	☐ Tower Side Box (silver briefcase thing)
3	☐ Three (3) Lithium Polymer 12V ignition batteries
1	□ Multimeter
5	☐ Electrically actuated valve for inside setup
5	☐ Phillips head screwdriver
	Inside Setup
	Do what you can inside to keep yourself from frostbite as much as possible.
1	$\ \square$ Put two LiPo batteries in tower side box, in the white 3d printed battery holders.
2	\Box Make sure the actuator switch is off (big black one with a 1 and 0 painted on it), clicked to "0".
3	\square Plug in both batteries. Lights on arduino should light up, relays should click.
1	\Box Wire electric valve into the relay board labelled RFV (remote fill valve):
5	☐ Blue wire screwed into V1
)	☐ Red wire screwed into V2
7	☐ White wire screwed into G1
8	☐ Black wire screwed into G2
9	☐ Make sure no wire strands are poking out of screw terminal
0	☐ Turn on actuator switch:
1	☐ If remote valve previously wasn't closed, it should now close. If not, go to troubleshooting guide.
2	□ Put battery in client side box. It plugs into the deans connector underneath the cutout, and isn't secured to anything (to be fixed).
3	☐ Turn on client side box (flip power switch).
4	☐ Confirm that LCD lights up.
5	\square Turn keyswitch 90 degrees clockwise.
6	☐ Confirm that missile switches light up.

17	☐ Flip Fill missile switch
18	\square Confirm that Electrically actuated valve turns to open
19	\square Confirm that there is no voltage from V1 to G1 on ignition relay board
20	\square Confirm that there is no voltage from V2 to G2 on ignition relay board
21	☐ Flip Primary Ignition Arm missile switch and depress fire button
22	\square Confirm that there is 12V from V1 to G1 on ignition relay board
23	$\ \square$ Confirm that there is no voltage from V2 to G2 on ignition relay board
24	\square Have that person unflip Primary Ignition Arm switch and flip Secondary Ignition Arm switch, and depress fire button
25	$\ \square$ Confirm that there is no voltage from V1 to G1 on ignition relay board
26	$\ \square$ Confirm that there is 12V from V2 to G2 on ignition relay board.
27	☐ Disconnect electrically actuated valve from RFV relay board
	End inside checks
	Outside setup
1	\square Find a good spot to put the tower side box. Put the tower side box there
2	☐ Connect remote fill valve to relay board labelled RFV:
3	\square Blue wire to V1
4	☐ Red wire to V2
5	\square White wire to G1
6	\square Black wire to G2
7	\square Make sure no wire strands are poking out of screw terminal
8	\square Connect tank vent valve to relay board labelled RVV:
9	\square Blue wire to V1
10	☐ Red wire to V2
11	\square White wire to G1
12	\square Black wire to G2
13	☐ Make sure no wire strands are poking out of screw terminal
14	☐ Connect injector valve to relay board labelled IJV:
15	\square Blue wire to V1
16	☐ Red wire to V2
17	\square White wire to G1
18	☐ Black wire to G2
19	\square Make sure no wire strands are poking out of screw terminal
20	$\ \square$ Ensure that ignition transmission cables are not connected to the rocket
21	\square Connect ignition transmission cables to relay board labelled IGN:
22	$\ \square$ Primary coil wires to V1 and G1 (polarity is irrelevant)

23	\square Secondary coil wires to V2 and G2 (polarity is irrelevant)
24	\square Make sure no wire strands are poking out of screw terminal
25	☐ Perform "Outside Tests" Procedure
26	☐ Disconnect both LiPos in tower side box to conserve power
27	☐ Turn off client side box to conserve power
	End of setup procedure
	Outside Checks
	Perform during outside setup procedure and again immediately before test
1	☐ Turn on client side box (Ensure LCD lights up)
2	☐ Turn key switch (Ensure missile switches light up)
3	☐ Turn on tower side box actuator switch
4	$\ \square$ Confirm that all three electrically actuated valves are closed
5	☐ Flip Fill missile switch
6	☐ Confirm that remote fill valve opened
7	☐ Un-flip Fill switch
8	☐ Confirm that remote fill valve closed
9	☐ Flip Tank Vent missile switch
10	\square Confirm that remote vent valve opened
11	☐ Un-flip Tank Vent switch
12	\square Confirm that remote vent valve closed
13	☐ Flip Injector missile switch
14	\square Confirm that injector valve opened
15	☐ Un-flip Injector switch
16	\square Confirm that injector valve closed
	The remainder of these checks are for the ignition system. They are unnecesary for cold flow test. This would be the end of checks for the cold flow procedure.
17	\square Approach ignition leads (female quick connect side)
18	$\ \square$ Confirm that the ignition leads are not connected to the rocket.
19	\square Probe for voltage across primary leads
20	\square Confirm that multimeter reads 0 volts
21	☐ Flip Primary Ignition Arm missile switch
22	\square Confirm that reading is still 0 volts
23	☐ Press Fire button

24	$\hfill\Box$ Confirm that multimeter now reads 12 volts
25	☐ Release Fire button
26	$\hfill\Box$ Confirm that multimeter now reads 0 volts
27	☐ Un-flip Primary Ignition Arm missile switch
28	$\hfill\Box$ Probe for voltage across secondary leads
29	$\hfill\Box$ Confirm that multimeter reads 0 volts
30	☐ Flip Secondary Ignition Arm missile switch
31	$\ \square$ Confirm that reading is still 0 volts
32	☐ Press Fire button
33	$\hfill\Box$ Confirm that multimeter now reads 12 volts
34	☐ Release Fire button
35	$\hfill\Box$ Confirm that multimeter now reads 0 volts
36	☐ Un-flip Secondary Ignition Arm missile switch
37	☐ Un-flip all missile switches
38	☐ Turn off client side box
	End of Checks procedure